

Standarta komplektācija:
<b>1 Pārvietojama moduļa ēka</b> * sienas, grīdas, pārsegumi, jumta konstrukcija <b>2 Izolācija:</b> * ārsienās - 150mm minerālvate Isover KL35; * grīdā, griestos - 200mm minerālvate Isover KL35; * vēja un tvaika barjeras membrānas; <b>3 Fasādes apdare</b> - koka apdares dēļi (priede/egle) krāsoti; <b>4 Jumta segums;</b> <b>5 Terase ar nojumi;</b>
Piezīmes: * Cenā nav iekļauta moduļu piegāde; * Apdares darbi par papildus samaksu;

Стандартная комплектация:
<b>1 Модульная мобильная здание</b> * стены, полы, конструкции крыши <b>2 Изоляция:</b> * наружные стены 150 мм Isover KL35; * потолок, пол 200 мм Isover KL35; * пара и ветра барьерные мембраны; <b>3 Отделка фасады</b> - деревянные доски (сосна / ель) окрашены; <b>4 Кровля;</b> <b>5 Терраса с навесом;</b>
Примечания: * Цена не включает доставку; * Отделочные работы за дополнительную плату;

Standard complete set:
<b>1 Modular mobile house</b> external walls, floors, ceiling, roof constructions <b>2 Insulation:</b> * external walls -150mm wool Isover KL-35; * ceiling, floor -200mm wool Isover KL-35; * vapor and wind barrier membranes; <b>3 Facade decoration</b> - wooden planks (pine / spruce) painted; <b>4 Roof cover;</b> <b>5 Terrace with a shelter;</b>
Notes: * Price does not include delivery; * Finishing works for an additional fee;