

Standarta komplektācija:

**1 Divu moduļu ēka**

\* sienas, grīdas, starpsienas, pārsegumi, jumta konstrukcija

**2 Izolācija:**

\* ārsienās - 150mm minerālvate Isover KL35;

\* grīdā, griestos - 200mm minerālvate Isover KL35;

\* vēja un tvaika barjeras membrānas;

**3 Fasādes apdare** - koka apdares dēļi (priede/egle) krāsoti;

Piezīmes:

\* Cenā nav iekļauta moduļu piegāde;

\* Apdares darbi par papildus samaksu;

Стандартная комплектация:

**1 Двух модульное здание**

\* стены, перегородки, полы, конструкции крыши

**2 Изоляция:**

\* наружные стены 150 мм Isover KL35;

\* потолок, пол 200 мм Isover KL35;

\* пара и ветра барьерные мембраны;

**3 Отделка фасады** - деревянные доски (сосна / ель) окрашены;

Примечания:

\* Цена не включает доставку;

\* Отделочные работы за дополнительную плату;

Standard complete set:

**1 Two modular building**

external walls, floors, partition walls, ceiling, roof constructions

**2 Insulation:**

\* external walls -150mm wool Isover KL-35;

\* ceiling, floor -200mm wool Isover KL-35;

\* vapor and wind barrier membranes;

**3 Facade decoration** - wooden planks (pine / spruce) painted;

Notes:

\* Price does not include delivery;

\* Finishing works for an additional fee;