

## Calculation

MEHĀNISKĀS DARBNĪCAS, ROPAŽI, ROPAŽU.NOV., LV-2135 e-pasts: info@woodpanelhouses.eu, tālr.+371 - 2 64 89 860

## **BANDITA**

## **Energy-efficient all-season LIVING HOUSE**

Premises area **144,9** m<sup>2</sup> Heated garage

Shed Area **42** m<sup>2</sup>

Nr.	Completion:		
1	HOUSE CONSTRUCTION WITH THERMAL INSULATION		
*	exterior wall panels WPH _200_W	insulation 250mm	
*	partition panels WPH_100	insulation 100mm	
*	floor panels WPH_250_B	insulation 300mm	
*	roof trusses	insulation 500mm	
		PRICE (VAT excluded 21%)	37 451.47 €

2 ICONSTRUCTION ASSEMP	Iν	

- 3 BASIC steel screw piles
- 4 ROOF COVERING steel sheets
- 5 CORNICES wood trim boards, painted
- 6 GUTTERS AND DRAINS steel
- 7 FACADE wooden boards, painted in 2 layers;
- 8 WINDOWS PVC , 3 glass;
- 9 EXTERIOR DOORS- PVC, 3 glass;
- 10 Garage gates
- 11 | CEILING gypsum board on metal profiles
- 12 WALL gypsum board 2 layers
- 13 HEATED CONCRETE FLOORS
- 14 WIRING switches, sockets, lamps, automatic switches;
- 15 | SEWERAGE AND WATER PIPE SYSTEM

PRICE TOTAL (VAT excluded 2	21%) 85 123,98 €
VAT 21%	17 876,04 €
PRICE TOTAL (VAT included 2	21%) 103 000,02 €

PRICE (VAT excluded 21%)

47 672,51 €

The price is to be adjusted upon the attraction of a home project to a particular building site.

Wood Panel Houses Ltd. reserves the right to change prices without prior notice.